

Re- Quotation Notice

Competitive quotations are invited from interested vendors within Kerala for rewiring of the networking facility in the LLB Section, First Floor of the Main Building, Senate House Campus.

(Specifications appended)

Conditions

1. The rate quoted should be inclusive of Tax, transportation charges, installation charges and any other charges.
2. Complaints with the items supplied should be rectified/replaced to the satisfaction of the University by the suppliers at their own cost.
3. Payment will be made only after the supply and installation of the items at our site.
4. The undersigned reserves the right to reject/accept any quotation without assigning any reason.

The sealed quotations should be addressed to the undersigned superscribing as “**Quotation for rewiring of networking facility at the LLB Section, First Floor of the Main Building, Senate House Campus, Palayam**”. The last date of receipt of quotations is at 3:00 p.m. on 08.11.2024. The quotations will be opened at 3:30 p.m. on the same day in the presence of the vendors then present.

REGISTRAR



Specification

Estimate for Networking for the LLB Section, Main Building, SH Campus, University of Kerala.						
Materials						
Sl. No	Item	Qty	Unit	Unit rate	Estimated cost	Make / Model
1	Cat6 UTP Cable (Molex/AMP/NORDEN)	300	Mtr			
2	Information Outlet (Molex/AMP/NORDEN)	19	Nos.			
3	Singleshutter faceplate	19	Nos.			
4	3/3 SMB (box)	19	Nos.			
5	25mm White ISI PVC Pipe with accessories	110	Mtr			
6	Cat 6 1mtr Patch cord - Molex or equivalent	19	Nos.			
7	Cat 6 2mtr Patch cord - Molex or equivalent	19	Nos.			
8	24 port Cat 6 patch panel - Fully loaded - Dlink/Molex/equivalent	1	Nos.			
9	24 Port 1000 Mbps Manageable Switch with 2 Nos. of 1 G SFP Ports, Lifetime warranty (HP/Netgear/Cisco) and Should support HP - JD119B 1 G SFP Transceiver.	1	No.			
Labour						
10	Cat6 UTP Laying Charges	300	Mtr			
11	RJ 45 / IO Termination Charges	19	Nos.			
12	Faceplate Fixing Charges	19	Nos.			
13	3/3 PVC Box fixing Charges (Surface)	19	Nos.			
14	Fixing and ports termination of Patch panel.	1	Nos.			



15	20mm/25mm/32mm white PVC Pipe Laying Charges through surface	110	Mtr			
16	Fixing and Configuration of Switch	1	Nos.			
17	Testing, Commissioning and Labeling of Network	1	Nos.			
18	Unforeseen items	1	Nos.			
Total						

The Guarantee of the items shall be specified in the quotation.

