

Quotation Notice

Competitive quotations are invited from interested vendors within Kerala for provision of networking facility in the PCVC T(1) Section- Old SDE Building, Senate House Campus, University of Kerala, Palayam.

(Specifications appended)

Conditions

1. The rate quoted should be inclusive of Tax, transportation charges, installation charges and any other charges.
2. Complaints with the items supplied should be rectified/replaced to the satisfaction of the University by the suppliers at their own cost.
3. Payment will be made only after the supply and installation of the items at our site.
4. The undersigned reserves the right to reject/accept any quotation without assigning any reason.

The sealed quotations should be addressed to the undersigned superscribing as **“Quotation for provision of networking facility in the PCVC T(1) Section- Old SDE Building, Senate House Campus, University of Kerala, Palayam”**. The last date of receipt of quotations is at 3:00 p.m. on 05.08.2024. The quotations will be opened at 3:30 p.m. on the same day in the presence of the vendors, then present.

REGISTRAR



Specifications

Estimates for providing additional structured network connection at the PCVC T (1) Section, Old SDE Building,SH Campus, University of Kerala

Sl.No.	Item	Qty	Unit	Amount	Total
1	Cat 6e UTP Cable (Molex/AMP/Commscope/ NORDEN)	140	Mtr		
2	Information Outlet (Molex/AMP/Commscope/ NORDEN)	8	Nos.		
3	Single Shutter Faceplate	8	Nos.		
4	3/3 SMB (box)	8	Nos.		
5	20mmWhite ISI PVC Pipe with accessories	25	Nos.		
6	25mmWhiteISIPVCPipe with accessories	40	Mtr		
7	24 port Cat 6e patch panel- Fully loaded- Commscope/Molex/equivalent	1	Mtr		
8	Cat6e 1 mtr Patch Cord-Molex or equivalent	8	Nos.		
9	Cat6e 2mtr Patch cord-Molex or equivalent	8	Nos.		
10	Cable Manager - 1 U	1	Nos.		
11	24 Port 1000Mbps Unmanageable Switch with Lifetime Warranty (HP/Netgear/Cisco)	1	Nos.		
Labour					
12	Cat 6e UTP Laying Charges	140	Mtr		
13	RJ45/IO Termination Charges	8	Nos.		
14	Faceplate Fixing Charges	8	Nos.		
15	3/3PVCBox fixing Charges (Surface)	8	Nos.		



16	Fixing and ports termination of 24 Port Patch panel.	1	No.		
17	Fixing and Configuration of Switch	1	No.		
18	20mm/25mm/32mmwhite PVC Pipe Laying Charges through surface	65	No.		
19	Testing, Commissioning and Labeling of Network	1	Mtr		
Total					

The Guarantee of the items shall be specified in the quotation.

